

**Vidyasagar Central Co-operative
Bank Ltd., Midnapore**
Head office: - Midnapore
At & P.O. - Midnapore



Telephone – 03222-275417, 275411
FAX - 03222 - 275411
E-mail – vccbmidnapore@gmail.com
Dist. - Paschim Medinipur

Memo- Dev /196

Date- 03/02/2020

Notice Inviting Quotation

Notice inviting quotations for Supplying and Fixing PVC Floor Mat and Aluminum Window at Khargapur Branch 1st Floor of Vidyasagr CCB Ltd., Midnapore At Koushallya, Post: Khargapur; Dist :-Paschim Medinipur .

Sealed item rate quotations are hereby invited from reputed & experienced person /contractors/firm.

Name of work: - Supplying and Fixing **PVC Floor Mat and Aluminum Window** at Khargapur. 1st Floor all Rooms as per specification at Khargapur Branch, At- Koushallya, Post: Khargapur, Dist. :- Paschim Medinipur and providing materials (approved) as required for.

Location/Place: - *Vidyasagar Central Co-operative Bank Ltd., Midnapore, Head Office.*

Completion time:- *15 days from the date of issue of work order.*

Last date & time of submission of Quotation:- *17/02/2020 up to 12 noon*

Date & time of Opening of Quotation:- *17/02/2020 at 3 pm*

Description of works :- *Work should be done as per the design and instruction given by Engineer/ authority of the Bank.*

Terms & condition : **Supporting documents should be submitted in qualification bid and also will have to be submitted PT, Trade license. Clearance certificate, PAN CARD, GST Registration.**

- 1)** All bid must be accompanied by a refundable earnest money / bid security amount to Rs.2000/- as mentioned in the form of Bank Draft / Bankers Cheques in favour of Vidyasagar Central Co-Operative Bank Ltd., Midnapore .
- 2)** The quotation should indicate specifically the basic price ,taxes, other duties if any per sq.ft no additional information will be entertained after due date.
- 3)** No revision of rates shall be allowed except taxes / charges levied by the Central / State by dully notified only.
- 4)** No advance or running payment shall be made. Payment shall be released after the satisfactory work as mentioned above and providing & fixing of allied works
- 5)** No deviation from the specification shall be allowed without prior consent of authority.
- 6)** All rubbish and superfluous materials shall be removed from site at the cost of contractor after the completion of work and prior to submission of final bill. Rubbish may be disposed outside of premises.
- 7)** The contractor shall make arrangements for storage of material, tools and equipment etc at the site and Bank shall not bear any expenses and risks also on this account.

8) The contractor shall observe all necessary precautions at his cost to safeguard the workers during execution of work.

9) 90% payment against inspection acceptance delivery and completion of works and balance 10% will be paid after 6 months of warranty period. And also that the Payment will be made on successfully completion of work as per work order through account payee cheque or by transfer through NEFT/ RTGS .

10) The undersigned is the accepting authority who reserves the right to reject any or all quotations without assigning any reason and any notice or he will not bound to accept either the lowest tender at any of the bidders.

For further details please contact P & D Section , H.O. Midnapore or see notice Board of the Bank or visit our Banks website www.vidyasagarccb.in

Date:- 03/02/2020

General Manager

Renovation KHARGAPUR BRANCH of Vidyasagar Central Co-Operative Bank by Fixing Aluminum Sliding Window, At- Koushallya, P.O- Khargapur, Dist: Paschim Medinipur ; PLOT NO- , JL NO-

Sl. No.	Description of Item	Length	Bredth	Height	Nos	Quantity	Unit	Rate	Amount
									Rs.
1	Supplying for Armstrong PVC Floor made of 2 mm thk pvc floor layng for serfacing compund filler and leabeling and Adhesive pesting.	10.4	7.55		1	844.75	SFT		0.00
		4.4	3		1	142.01	SFT		0.00
		8.5	5.9		1	539.53	SFT		0.00
	Total								0.00
								GST @ 18%	0.00
								CGST 9%	0.00
								SGST 9%	0.00
TOTAL									0.00

**Renovation KHARGAPUR BRANCH of Vidyasagar Central Co-Operative Bank by Fixing Aluminum Sliding Window,
At- Koushallya, P.O- Khargapur, Dist: Paschim Medinipur ; PLOT NO- , JL NO- .**

ALL RATES ARE TAKEN FROM W.B PWD SCHEDULE 2015

FIRST FLOOR INCLUDING Stair Area of KGP Branch

SL.NO	DESCRIPTION OF WORK	Length	Bredth	Height	Nos	QTY.	UNIT	RATE RS.	AMOUNT RS.
1	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In- Charge. (Payment will be made on finished length of the work). (A) In 10-12 Micron thickness Anodizing film l) Natural white a) 2- track sliding window i) Bottom frame, Top and side Frame (Item No: 1 , Page No: 206)	4	5		5	100.00	Sq Ft		0.00
		3.5	4.75		1	16.63	Sq Ft		0.00
		3	4		3	36.00	Sq Ft		0.00
		3	4		5	60.00	Sq Ft		0.00
						0.00	Sq Ft		0.00
						0.00	Sq Ft		0.00
						0.00	Sq Ft		0.00
						0.00	Sq Ft		0.00
						0.00	Sq Ft		0.00
						0.00	Sq Ft		0.00
Total=								0.00	