

Vidyasagar Central Co-operative  
Bank Ltd., Midnapore  
Head office: - Midnapore  
At & P.O. - Midnapore,  
Dist. - Paschim Medinipur



Telephone – 03222–275417, 275411  
FAX - 03222 - 275411  
E-mail – vccbmidnapore@gmail.com

Memo- Dev /

Date- 08/05/2019

## **Notice Inviting Quotation**

**Sealed quotations are invited from reputed Supplier/Vendor for Supplying, fitting and fixing of Acoustic False ceiling made of Armstrong for Different Branches of Vidyasagar CCB Ltd., Midnapore for the FY 2019-20.**

**Name of work:** - Supplying, Fitting and Fixing of Acoustic False Ceiling made of Armstrong of 15.0 mm thk. supported by necessary Galvanized steel frame work for Narayangarh Branch, Balichak Branch and others'.

*Location/Place:* - Vidyasagar Central Co-operative Bank Ltd., Midnapore, Head Office.

*Completion time:*- 45 days after the issuing of Work order .

*Last date & time of submission of Quotation:*- 24/05/2019 up to 12 noon

*Date & time of Opening of Quotation:*- 24/05/2019 at 3 pm

**Terms & condition :** Supporting documents should be submitted in qualification bid and also will have to be submitted PT , Trade license, PAN CARD, GST Registration.

### **Terms & Condition:-**

- 1) All bid must be accompanied by a refundable earnest money / bid security amount to Rs.10000/- as mentioned in the form of Bank Draft / Bankers Cheques in favour of Vidyasagar Central Co- Operative Bank Ltd., Midnapore or **preferably NEFT to A/C No : 123002048872 , IFSC : WBSC0VCCB39 .**
- 2) All above items will be supplied with in 15 days from the date of issue of purchase order.
- 3) The quotation should indicate the rate excluding all taxes.
- 4) No revision of rates shall be allowed except taxes / charges levied by the Central / State by dully notified only.
- 5) No advance or running payment shall be made. Payment shall be released after the satisfactory delivery of items and production of bill (in duplicate) in name of Vidyasagar Central Co- Operative Bank Ltd., Midnapore .
- 6) No deviation from the specification shall be allowed without prior consent of authority.
- 7) Payment will be made on successfully completion of work as per work order through account payee cheques or by transfer through NEFT/ RTGS .

- 8)** The undersigned is the accepting authority who reserves the right to reject any or all quotation without assigning any reason or he will not bound to accept either the lowest tender at any of the bidders.

*For further details please contact P & D Section , H.O. Midnapore or see notice Board of the Bank or visit to Bank's website [vidyasagarccb.in](http://vidyasagarccb.in).*

**Date:- 08/05/2019**

**General Manager**

# VIDYASAGAR Central Co-Operative BANK

## SCHEDULE FOR FALSE CEILING

For Narayangarh, Balichak Branch

SL.No.	DESCRIPTION OF ,WORKS	Qty.	Unit
1	<p>Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid U-1520 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c ) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 15mm thick OW Acoustic Board (Mineral Fiber Acoustic Ceiling Tiles) of approved patern and size 595mm X 595mm with NRC value &gt; 0.65 should be placed in the Grid module to form a False Ceiling. All complete as per the drawing &amp; directions of Engineer-in-charge.</p> <p>a) Acoustic False Ceiling (with 15mm thick OW Acoustic Board and E-Grid U-1520). of <b>Armstrong</b> Make</p>	6000	sft
2	CORNICE	200	Rft
<b>TOTAL</b>			

NB:

**GST EXTRA**