

**Vidyasagar Central Co-operative  
Bank Ltd., Midnapore**



Telephone - 03222-275417, 275411

FAX - 03222 - 275411

Head office: - Midnapore

At & P.O. - Midnapore,

E-mail - [vccbmidnapore@gmail.com](mailto:vccbmidnapore@gmail.com)

Dist. - Paschim Medinipur

---

**Memo- Dev/11**

**Date- 05/05/2021**

## **Notice Inviting Quotation**

**Notice inviting quotations for Repairing and Renovation of Khargapur Branch of Vidyasagar CCB Ltd., Midnapore at- Kaushallya, Post: Khargapur Dist.:- Paschim Medinipur and providing materials as required for.**

**Sealed item rate quotations are hereby invited from reputed & experienced person /contractors/firm.**

**Name of work:** - Repairing and Renovation of Khargapur Branch of Vidyasagar CCB Ltd., Midnapore by construction of Strong Room, repairing of store room, Toilet Renovation and other allied activities at- Kaushallya, Post: Khargapur Dist.:- Paschim Medinipur as per the direction and specification of engineer -in charge and providing materials (approved) as required for.

**Location / Place:** - *Vidyasagar Central Co-operative Bank Ltd., Midnapore, Head Office.*

**Completion time:-** *One month from the date of issue of work order.*

**Last date & time of submission of Quotation:-** *21/05/2021 up to 12 noon*

**Date & time of Opening of Quotation:-** *21/05/2021 up to 3 noon*

**Description of works :-** *Work should be done as per the design and instruction given by Engineer/ authority of the Bank.*

**Terms & condition :** **Supporting documents should be submitted in qualification bid and also will have to be submitted PT, Trade license. Clearance certificate, PAN CARD, GST Registration.**

**1)** All bid must be accompanied by a refundable earnest money / bid security amount to Rs.10000/- as mentioned in the form of Bank Draft / Bankers Cheques in favour of Vidyasagar Central Co- Operative Bank Ltd., Midnapore .

**2)** The quotation should indicate specifically the basic price ,taxes, other duties if any per unit rate. No additional information will be entertained after due date.

**3)** No revision of rates shall be allowed except taxes / charges levied by the Central/State by dully notified only.

**4)** No advance or running payment shall be made. Payment shall be released after the satisfactory work as mentioned above and providing & fixing of allied works

**5)** No deviation from the specification shall be allowed without prior consent of authority.

**6)**All rubbish and superfluous materials shall be removed from site at the cost of contractor after the completion of work and prior to submission of final bill. Rubbish may be disposed outside of premises.

**7)** The contractor shall make arrangements for storage of material, tools and equipment etc at the site and Bank shall not bear any expenses and risks also on this account.

**8)**The contractor shall observe all necessary precautions at his cost to safeguard the workers during execution of work.

**9)** 90% payment against inspection acceptance delivery and completion of works and balance 10% will be paid after 6 months of warranty period. And also that the Payment will be made on successfully completion of work as per work order through account payee cheque or by transfer through NEFT/ RTGS .

**10)** The undersigned is the accepting authority who reserves the right to reject any or all quotations without assigning any reason and any notice or he will not bound to accept either the lowest tender at any of the bidders.

**For further details please contact P& D Section , H.O. Midnapore or see notice Board of the Bank or visit our Banks website [www.vidyasagarccb.in](http://www.vidyasagarccb.in)**

**Date:- 05/05/2021**

**General Manager**

# Vidyasagar Central Co-Operative Bank Ltd., Midnapore

## Estimate for VCCB, Khargapur Branch

KGP vault and Toilet Repairing Work

Sl. No.	Item Description	Length	Width	Height	Nos	Quantity	Units	Per unit Rate	TOTAL AMOUNT
1	Dismantling terraced roof in ground floor roof (including floor finish, if any.) taking out carefully tiles with beams, joists, tees or burgahs covering floor below, sorting and stacking sevicable materials at site and removing rubbish as directed within a lead of 75 m. In First Floor Roof	6	4		1	24	Sqm		-
		6	3		1	18	Sqm		-
		4	3		1	12	Sqm		-
		2.5	2		2	10	Sqm		-
		1.75	2		1	3.5	Sqm		-
	<b>( Item No 4, Page No 8 )</b>					0	Sqm		-
2	Earth work in filling in foundation trenches or plinth with silver sand in layers not exceeding 150 mm including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work.). With earth obtained from excavation of foundation	6	1.5	0.3	1	0.027	%Cum		-
								%Cum	
3	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (i) Tor steel/Mild Steel II. Other than SAIL/ TATA/RINL (b)Add extra over the rate of ground floor/initial 4 m for each basement floor and each additional floor below/ above ground floor (i) Upto 4 th floor roof in each addl. Floor					0.86	MT		-
4	Cement concrete (1:1.5:3) with graded stone chips 5.6 mm size with hexagonal square mesh wire netting, I.R.C. fabric mesh or X.P. M. fitted and fixed after tying the existing reinforcement on concrete without distributing the same and with proper scarping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement including the cost of wire netting I.R.C or X. P. M. & cost of all handling and scaffolding complete as per direction of Engineer-in -charge. (a) M 20 Grade  25mm Thick Concrete ( For First Floor Addl. Rs. 44/-) <b>( Item No 18 Page 29 )</b>	5	1.5		1	7.5	Sqm		-
		4	0.75		1	3	Sqm		-
						0	Sqm		-
						0	Sqm		-
						0	Sqm		-
						0	Sqm		-
5	125mm thick Brick work with First class Bricks in cement mortar (1:4) in Ground Floor	5	1.5		1	7.5	SQM		-
		4	0.75		1	3	SQM		-
6	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]  (ii) With 1:4 cement mortar (a) 15 mm thick plaster					40	SQM		-
						18	SQM		-
						15	SQM		-
							SQM		-
							SQM		-
							SQM		-
7	Controlled Cement concrete with well graded stone chips (20 mm graded nominal size) excluding shuttering and reinforcement with complete design of concrete as per IS : 456 and relevant special publications, submission of job mix formula after preliminary mix design after testing of concrete cubes as per direction of Engineer-in charge. Consumption of cement will not be less than 300 Kg of cement with Super plasticiser per cubic meter of controlled concrete but actual consumption will be determined on the basis of preliminary test and job mix fomula. In ground floor and foundation. [using concrete mixture] (a) M 20 Grade					4.00	Cum		-
						3.00	Cum		-

	(i) Pakur Variety Page No : 13 Item No : 6 a)					2.00	Cum		-
8	Neat cement punning about 1.5mm thick in wall,dado,window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. Item No : 08 , Page No : 166	8	6		2	96	Sqm		-
		8	3		4	96	Sqm		-
9	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns , lintels curved or straight including fitting, fixing and striking out after completion of work (upto roof of ground floor)	6	4		1	24	Sqm		-
		6	3		1	18	Sqm		-
						0	Sqm		-
						0	Sqm		-
						0	Sqm		-
10	Supplying, fitting & fixing Cast iron soil pipe only conforming to I.S. 3989/2009 and I.S. 1729/2002 with bobbins, nails etc. including making holes in the wall, floor etc. and cutting trenches etc. in any floor through masonry concrete, if necessary, and mending good damages with necessary jointing materials and painting two coats to the exposed surface with approved paint complete. (Measurement will be made along the center line of the total pipe line in fitted condition including specials,payment for specials & Painting will however be paid seperately).  a) With valamoid joints including sealing with sand cement mortar (4:1) upto quarter depth.					12.00	Rmt		-
11	All kinds of CPVC and other pipes and Fittings fully complete including Wash Basin, Comod, Urinal and Water Closet					1.00	L.S.		-
12	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile (B) Floor With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91Kg/Sq.m & joint filling using white cement slurry @0.20kg/Sq.m.	3	2		1	6.00	Sqm		-
	(b) Area of each tile above 0.09 Sq.m (ii) Other than Coloured decorative including white ( Item No : 30, Page No 54 )	6	2.5		1	15.00	Sqm		-
13	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile (B) Wall With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91Kg/Sq.m & joint filling using white cement slurry @0.20kg/Sq.m.	4.2	2.5		2	21	Sqm		-
	(b) Area of each tile above 0.09 Sq.m (ii) Other than Coloured decorative including white ( Item No : 30, Page No 54 )	6.5	2.5		1	16.25	Sqm		-
							<b>Total=</b>	<b>Rs.</b>	<b>-</b>

CGST @ 9% = Rs. -  
SGST @ 9% = Rs. -

**Grand Total = Rs. -**